BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/09/2020-21 Dated: 29-01-2021

APPROVED TENDER SCHEDULE –'B'

Item 09

Name of Work :-Improvements to Roads and Drains at Akshyanagara and Surrounding area in Ward No 03

Sl	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri R SHIVARAM	
				Rate	Rate in Words
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete As per Engineer In-Charges	Cum	1001.88	217.25	Two Hundred Seventeen Paise TwentyFive Only
2	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. As per Engineer In-Charges	Cum	150.28	5765.51	Five Thousand Seven Hundred SixtyFive Paise FiftyOne Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm As per Engineer In-Charges	Cum	327.89	7523.73	Seven Thousand Five Hundred TwentyThree Paise SeventyThree Only

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾ.
ಯಲಹಂಕ ವಿಭಾಗ

	Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, As per Engineer In-Charges	Tonne	21.31	68071.58	SixtyEight Thousand SeventyOne Paise FiftyEight Only
5	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete.(Data Rate) As per Engineer In-Charges	Sqm	819.72	2445.67	Two Thousand Four Hundred FourtyFive Paise SixtySeven Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.